

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: NOBLE ENERGY, INC.
Address: 100 GLENBOROUGH, #100, HOUSTON, TX 77067
Phone: (281) 872-3100 Operator License #: 33190
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10/06/2003 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
NIORARA Depth to Top: 1487 Bottom: 1508 T.D. 1682

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-023-20500-00-00
Lease Name: ZWEYGARDT
Well Number: 32-32
Spot Location (QQQQ): SW - NE - E
1980 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 32 Twp. 3 S. R. 41 East West
County: CHEYENNE
Date Well Completed: 10/06/2003
Plugging Commenced: 10/06/2003
Plugging Completed: 10/06/2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
NIORARA	GAS & WATER	1487	1508	7"	308'	0'

RECEIVED
OCT 28 2003
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
PLUGGED WELL W/60:40 POZ MIX CEMENT W/6% GEL AS FOLLOWS: 100 SX CMT @ 1364', 40 SX CMT 1/2 IN & 1/2 OUT OF BOTTOM OF SURFACE CSG (CSG SET @ 314') AND 10 SX CMT @ TOP OF SURFACE. CUT OFF CSG 4' BELOW SURFACE. Plug #1 from 1364' - 550' (814'), Plug #2 from 476'-166' (310') and Plug #3 from 79'-4' (75')

Name of Plugging Contractor: EXCELL DRILLING COMPANY License #: 28085 Pa73
Address: P.O. BOX 305, WRAY, CO 80758-0305

Name of Party Responsible for Plugging Fees: NOBLE ENERGY, INC.
State of TEXAS County, HARRIS, ss.


PATRICIA JAENECKE, REGULATORY SPECIALIST III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Patricia Jaenecke

(Address) 100 GLENBOROUGH, #100, HOUSTON, TX 77067



PATSY J. NEVILL
NOTARY PUBLIC STATE OF TEXAS
MY COMMISSION EXPIRES
NOV 27 2003
My Commission Expires: 11-28-04



CEMENTER'S WELL SERVICE, INC.
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE
183492

Noble

Date <i>10-06-03</i>	Well Owner <i>Energy Inc.</i>	Well No. <i>32-32</i>	Lease <i>Zuliygord</i>
County <i>Cherokee</i>	State <i>Kansas</i>	Field	
Charge to <i>Excell Drilling Company</i>	Charge Code		
Address <i>Rig # 2</i>	For Office Use Only		
City, State <i>Wray, Colorado, 80758</i>			
Pump Truck No. <i>1204</i>	Code	Bulk Truck No. <i>1211</i>	Code
Type of Job	Depth	Ft.	To
Surface	Bottom of Surface	Ft.	To
Plug <i>3 1/2" D.P</i>	Plug Landed @	Ft.	Time On <i>02:00</i>
Production	Pipe Landed @	Ft.	Time Off <i>04:45</i>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <i>✓</i>				
	Poz. Mix <i>✓ 60/40</i>	<i>150</i>	<i>SKS</i>		
	Calcium Chloride				
	Gel <i>6 %</i> Flo-Cele <i>1/4</i> #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	<i>1st plug @ 1364' w 100 SKS</i>				
	<i>2nd plug @ 280 1/2 in 1/2 out of surface casing w 40 SKS</i>				
	<i>2nd plug @ Top of surface casing w 10 SKS</i>				
	<i>Mixing Rate 4BPM - Displacement Rate 6BPM</i>				
	<i>Slurry Vol 1.19 CU FT/SK - Slurry WT 15.2 PPG</i>				

RECEIVED
 KANSAS CORPORATION COMMISSION
 OCT 28 2003
 CONSERVATION DIVISION
 WICHITA, KS

Remarks:	Tax Reference Code	Sub Total
	<i>Rate 5.49 %</i>	Tax
	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<i>1204</i>	Pump Truck			<i>40</i>		<i>15</i>	
<i>1211</i>	Bulk Truck			<i>40</i>		<i>15</i>	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By *Leary, John, Randy*

Received By *[Signature]*
 Customer or His Agent