

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-195-21,072 00 00

LEASE NAME Werth A

WELL NUMBER 1

4290 Ftt. from S Section Line

1650 Ftt. from E Section Line

SEC. 18 TWP. 13 RGE. 21 (E) or (W)

COUNTY Trego

Date Well (Completed) 12-01-02

Plugging Commenced 11/26/03

Plugging Completed 11/26/03

RECEIVED

DEC 10 2003 NOTICE: Fill out completely and return to Cons. Div. office within 30 days.
 KCC WICHITA

LEASE OPERATOR Encore Operating Co.

ADDRESS 1601 Blake St. Suite 500 Denver, Colorado

PHONE# (303) 595-9251 OPERATORS LICENSE NO. 33069

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 26, 2003 (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top 3898' Bottom 3913' T.D. 4150'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing	0	247	8 5/8"		none
	Producing Casing	0	4147	5 1/2"		none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Ran 2" tubing to 2050' circulated cement to surface with 190 sacks of 60/40 POS with 10% Gel and 500 lbs of hulls, pulled tubing and pumped 90 sacks of cement down the 5 1/2" casing at 400 pounds pressure ISIP 200 pounds. Pumped 10 sacks of cement down the 8 5/8" casing at no pressure. Cement in 5 1/2" casing from surface to 3913', port collar at 1647'.

Name of Plugging Contractor Chito's Well Service LLC License No. 32028 99998

Address Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Encore Operating Co.

STATE OF Colorado COUNTY OF Denver, s.s.

Roland Nyp (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 MAIN - STOCKTON KS 67669

AND SWORN TO before me this 4th day of December, 12 2003



Irene R Nyp
 Notary Public

My Commission Expires: 9-30-04