

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-19061-00-00
API NUMBER 5/16/59

RECEIVED
DEC 08 2003
WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Dreiling F
WELL NUMBER 9
330 FNL
4950 Ft. from S Section Line
990 Ft. from E Section Line
SEC. 3 TWP. 12 RGE. 16 (Eior)
COUNTY Ellis
Date Well Completed 5-16-59
Plugging Commenced 12-3-03
Plugging Completed 12-3-03

LEASE OPERATOR Dreiling Oil, Inc.
ADDRESS Box 550 Hays, KS 67601
PHONE (785) 625-8327 OPERATORS LICENSE NO. 5145

Character of Well Oil
(Oil, Gas, DSA, SWD, Input, Water Supply Well)
The plugging proposal was approved on 12-3-03 (date)

by Jay Pfeifer (KCC District Agent's Name)
Is ACO-1 filled? Yes If not, is well log attached? _____

Producing Formation Topeka Depth to Top 2744 Bottom 2750 T.O. 3410
2850
Give depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		CASING RECORD				
Formation	Content	From	To	Size	Put In	Pulled out
Topeka	oil, gas, water	2697	2958	8 5/8"	975'	-0-
Tornoto	oil, gas, water	2979	2992	5 1/2"	3409 3410	-0-
L-KC	oil, gas, water	3007	3228			
Arbuckle	oil, gas, water	3340	3382			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.
Ran 2" tubing to 2680'. Spotted 125 sx. 60/40 poz. mix. 10% gel & 500# hulls. Pulled up to 1380'. Mixed 120 sx. 60/40 poz. mix & circ. to surface. Cement came up 8 5/8" casing. Closed in & pressured to 1400#. SIP-400# Pulled tubing & hooked to 5 1/2" - mixed 10 sx. Pressured to 550#. SIP-550#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service & Supply FNC. Allied Cementing Co., Inc. License No. 6426
Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dreiling Oil, Inc.
STATE OF Kansas COUNTY OF Ellis, ss.

Terry Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) Box 550 Hays, KS 67601

Notary Public State of Kansas
Patricia Dreiling
My Appt Exp SUBSCRIBED

AND SWORN TO before me this 4th day of December, ~~19~~ 2003

Patricia Dreiling
Notary Public

My Commission Expires: 8-23-06