

3 022523

15-001-01776-00.00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:30A.M. Day: _____ 2 Month: 12 2003Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSIONPhone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800" THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WASTO PERFORATE THE WELL SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THE WELLAS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN
☒ None _____Operations Completed: Hour: 10:00A.M. Day: _____ 2 Month: 12 2003Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 500', AND AT 350',AND THE 2" CASING WAS PERFORATED AT 200'. 3/4" PIPE WAS RAN INTO THE 2" CASINGTO 580'. CEMENT WAS PUMPED INTO THE 2" CASING UNTIL CEMENT CIRCULATED FROMTHE 2" CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE2" AND 8" ANNULUS TO 75'. CEMENT WAS CIRCULATED TO SURFACE. THE 1" PIPE WASREMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.Remarks: (THIS WELL WAS NOT INDICATED ON THE OLD LEASE MAP)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
DEC 15 2003
KCC WICHITA