

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21634-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 21-33S-33W
1250 feet from S Section Line, 1250 feet from W Section Line
Lease/Unit Name: MORGAN O Well Number: 1-H
County: SEWARD Total Vertical Depth: 2751 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 2751 WITH 300 SX CMT
Surface Casing Size: 8.625 feet: 545 WITH 200 SX CMT

#8941

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/10/2003 9:30 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCOBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: MIX AND PUMP 4 SX HULLS AND 32 SX CLASS H CEMENT FROM 2702' TO 2450'. SHOOT OFF 5-1/2" CASING @ 650' AND PUMP 32 SX CLASS H NEAT CEMENT FROM 350' TP 600'. PUMP 12 SX CLASS H NEAT CEMENT PLUG FROM 4' TO 100'. CUT OFF 8-5/8" CASING 4' BELOW GL AND PLACE 1/4" STEEL CAP ON CASING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/10/2003 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2690'. PERFS AT 2587-2690'. PUMP 400# HULLS WITH 50 SX CMT. LOAD HOLE WITH 55 BBL MUD. PRESSURE CASING TO 300 PSIG & SHUT IN. 1ST PLUG LOAD HOLE WITH MUD. PUMP 65 SX CMT AT 580'. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH CASING TO 40'. LOAD HOLE WITH MUD. PUMP 15 SX CMT TO SURFACE. STAYED FULL.

RECEIVED
DEC 16 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY PHIL DOLLAR OIL FIELD SVC. RECOVERED 666' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
DEC 12 2003
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 12-16-03
INV. NO. 2004060956

Form GP 4/2