

3 022521

15.001-01775-000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICELic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 11:30A.M. Day: _____ 2 Month: 12 2003Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISED OF 2" CASING TO APPROXIMATELY 800' THAT MAY HAVEBEEN CEMENTED IN FROM BPTTOM TO TOP. THE PLUGGING PROPOSAL WAS TOPERFORATE THE CASING SEVERAL TIMES AND TO CIRCULATE AS MUCH OF THE WELLAS POSSIBLE FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part ☒ Technician _____Operations Completed: Hour: 2:00P.M. Day: _____ 2 Month: 12 2003Actual Plugging Report: THE 2" CASING WAS PERFORATED AT 500', AT 350', AND THECASING WAS PERFORATED AT 200'. 3/4" PIPE WAS RAN INTO THE 2" CASING TO 756'.CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2"CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROMSURFACE.

INTO THIS WELL.

Remarks: (GPS SESSION POINT NO. 7)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED
DEC 15 2003
KCC WICHITA

Signed:


TECHNICIAN