

3 022515

15-207-19257-000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well Gas Well _____

API NUMBER	<u>SW SE SE</u>	N/A
NE, SE, NE 1/4	Sec/Twp/Rge S.12-T.25S.-R.15E.	
319 feet from south section line		
1086 feet from east section line		
Lease/Well#	<u>TRAHAN NO.TRA 01</u>	
County	<u>WOODSON</u>	
Well Total Depth	<u>900'</u>	feet
Production Pipe:	<u>2 7/8"</u>	Size Feet <u>900'</u>
Surface Casing:	Size Feet _____	
D & A	Size Feet _____	

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, L.L.C. Lic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 2:00P.M. Day: _____ 14 Month: 11 Year: 2003Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 950' THAT MAYHAVE BEEN CEMENTED IN FROM BOTTOM TO TOP. NO SURFACE CASING WAS EVIDENT.THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASING SEVERAL TIMES AND TOCIRCULATE THE CASING FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

None

Plugging attended by Agent: All Part _____Operations Completed: Hour: 3:30P.M. Day: _____ 14 Month: 11 Year: 2003Actual Plugging Report: THE 2 7/8" CASING WAS PERFORATED AT 700', AT 500', ANDTHE 2 7/8" CASING WAS PERFORATED AT 300. 1" PIPE WAS RAN INTO THE 2 7/8" CASINGTO 950'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2 7/8" AND 1" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. THE 2 7/8" WAS TOPPEDWITH CEMENT. A VALVE WAS ATTACHED TO THE TOP OF THE 2 7/8" CASING. CEMENT WASPUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELLWAS THEN SHUT IN AT 500P.S.I.. 47 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED

Signed:

Clayton P. Titel
TECHNICIAN

DEC 04 2003

KCC WICHITA