

RECEIVED
NOV 25 2003
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-135-30276-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 01-06-67.

Well Operator: Pickrell Drilling Company, Inc. KCC License #: 5123
(Owner / Company Name) (Operator's)

Address: 100 S. Main, Suite 505 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (316) 262-8427

Lease: Starrett B Well #: 2 Sec. 12 Twp. 17S S. R. 21 East West

- C - SE - NE Spot Location / QQQQ County: Ness

3300 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 406 Cemented with: 200 Sacks

Production Casing Size: 5 1/2 Set at: 4054 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open hole 4054-4059 plus 400 cu. ft. thru DV tool @ 1433

Elevation: 2168 (G.L. / K.B.) T.D.: 4059 P.B.T.D.: Same Anhydrite Depth: 1420 (+748)
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Use 60/40 cement, 6% gel. Tie into 8 5/8 x 5 1/2 annulus and fill and leave S.I. w/ pressure. Down 5 1/2 pump 2 sx hulls in water, pump 25 sx. cement w/ hulls in first few sacks, pump 50 bbls of gel (14 sx) mud, pump, pump 156 sx cement plus enough additional to pressure pipe. Leave SI w/ pressure.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____ (Suggest have 250 sx. cement on location)

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ed Mondero

Phone: (785) 798-2430

Address: P.O. Box 375 City / State: Ness City, Kansas 67560

Plugging Contractor: Allied Cementing Company, Inc. KCC License #: N/A
(Company Name) (Contractor's)

Address: N. Hwy 281, P.O. Box 628, Great Bend, KS 67530-0628 Phone: (620) 793-5861

Proposed Date and Hour of Plugging (if known?): November 26, 2003

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-24-03 Authorized Operator / Agent: _____

Jack J. Wiley
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

BAKER SERVICE TOOLS - TALLY PAD

New Completion Workover

Oil Company _____ Well No. 2 Field Start Lease Starrett B
 Company Man _____ Date Drilled 1966 County Ness State Kansas

API # 15-135-30276-00-00

JT. NO.	FT.	100 THS	JT. NO.	FT.	100 THS	JT. NO.	FT.	100 THS
1								
	- 40' TOC in 8 3/8 x 5 1/2 Annulus							
3								
4								
5								
	- 406 Base 8 7/8" w/200 SX							
7								
8								
9								
10								
11								
	- 1433 Stage Collar w/400 ft ³ 20% Diacel w/2% gel (Did not circ.)							
12								
13								
14								
15								
16								
17								
18								
19								
20								
21								
22								
23								
24								
25								

RECEIVED
 NOV 25 2003
 KCC WICHITA

Total
 - 4054 Base 5 1/2" 14.0 # S-55 w/100 SX.
 - 4058 (Orig. RTD)
 - 4059 (TD-1973)

REMARKS:

Feet on this page _____
 Average jt. lgth. this page _____

Date of Tally _____
 No. Jts. on Location _____
 Tbg. Sz. _____ Thd. _____ Wt. _____ Gr. _____
 Csg. Sz. _____ Wt. _____ Gr. _____



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Pickrell Drilling Company, Inc.
100 South Main - Suite 505
Wichita, KS 67202-3738

November 26, 2003

Re: STARRETT B #2
API 15-135-30276-00-00
SENE 12-17S-21W, 3300 FSL 660 FEL
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888