

RECEIVED
NOV 25 2003
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 173-20,265-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: Bear Petroleum, Inc. KCC License #: 4419
(Owner / Company Name) (Operator's)

Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: (316) 524 - 1225

Lease: Farber Well #: 1 Sec. 17 Twp. 29 S. R. 2 East West

C - SW/4 Spot Location / QQQQ County: Sedgwick

1470 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3960 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 130 Cemented with: 100 Sacks

Production Casing Size: 5 1/2 Set at: 3497 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open hole 3497-3507 10' top cement 2700'

Elevation: 1304 (G.L. / K.B.) T.D.: 3507 P.B.T.D.: 3507 Anhydrite Depth: ?
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand back to 3457', dump bail 5 sax cement or sand, shoot and pull 5 1/2", run pipe into 180', circulate cement to surface, pull pipe, top off well.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dick Schremmer

Bear Petroleum, Inc. Phone: (316) 524 - 1225

Address: P.O. Box 438 City / State: Haysville, KS 67060

Plugging Contractor: BPC Well Plugging KCC License #: ~~6957~~ 32475
(Company Name) (Contractor's)

Address: P.O. Box 282, Burden, KS 67107 Phone: (620) 438 - 2856

Proposed Date and Hour of Plugging (if known?): unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-24-03 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/04

6/04



BRANDT OIL COMPANY

1200 DOUGLAS BUILDING WICHITA, KANSAS 67202

• PHONE (316) 267-4335

RECEIVED
NOV 25 2003
KCC WICHITA

April 15, 1980

API # 15-173-20265-00-00

GEOLOGICAL REPORT
BRANDT OIL COMPANY

1 Farber
C-SW/4 Sec 17-29s-2E
Sedgwick County, Kansas

The following is a geological report covering the above described test. The test was geologically supervised from 1723' to total depth. Samples were examined from 2000' to total depth and a gas detector was operational from 1723' to total depth. Samples from the well have been placed on file with the Kansas Geological Survey. Drill Stem Tests were taken and open hole electrical surveys were performed by Petro-Log, Inc.

| | |
|--------------------|---------------------------|
| OPERATOR | Brandt Oil Company |
| Contractor | Brandt Drilling Co., Inc. |
| Location | C-SW/4 Sec 17-29s-2E |
| Elevation | 1304' Gl. 1309' Kb. |
| Drilling Commenced | April 5, 1980 |
| Drilling Completed | April 15, 1980 |
| Surface Casing | 8 5/8" @ 132' w/100sx |
| Production Casing | 5 1/2" @ 3490.5' w/175sx |

LOG TOPS

| | |
|-------------------|--------------|
| HEEBNER SH. | 2008 (-699) |
| IATAAN | 2256 (-947) |
| STALNAKER SAND | 2260 (-951) |
| KANSAS CITY | 2617 (-1308) |
| BASE KANSAS CITY | 2846 (-1537) |
| PAWNEE | 2906 (-1597) |
| FORT SCOTT | 2990 (-1681) |
| CHEROKEE | 3077 (-1768) |
| MISSISSIPPIAN LM. | 3113 (-1804) |
| KINDERHOOK SH. | 3402 (-2093) |
| CHATTANOOGA SH. | 3471 (-2162) |
| SIMPSON SAND | 3487 (-2178) |
| RTD | 3501 (-2192) |
| LTD | 3499 (-2190) |



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

November 26, 2003

Re: FARBER #1
API 15-173-20265-00-00
SW 17-29S-2E, 1470 FSL 3960 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231