

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20488-00-01
Spot: SW Sec/Twnshp/Rge: 8-21S-20W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: STEFFEN Well Number: 1
County: PAWNEE Total Vertical Depth: 4315 feet

Operator License No.: 32302
Op Name: KEY GAS CORP.
Address: 155 N. MARKET - SUITE 900
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4300 TOC @ 1150'
Surface Casing Size: 8.625 feet: 985

#140²⁴

Well Type: SWD UIC Docket No: D20151.0 Date/Time to Plug: 12/12/2003 10:00 AM

Plug Co. License No.: 32302 Plug Co. Name: KEY GAS CORP.

Proposal Rcvd. from: MIKE MCNAUL Company: KEY GAS CORP. Phone: (316) 662-6977

Proposed
Plugging
Method:

RUN TUBING TO 3030' & SPOT 30 SX CMT. PERFORATE @ 1000' AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/12/2003 3:45 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:


PERFS AT 4232-41'. COMPANY ATTEMPTED TO CLEAN OUT WELL. LEFT PACKER AND FIBERGLASS TUBING FISH. TOP OF FISH @ 3280'. COULDN'T GET LOG OR TUBING BACK FAST 3080'. RAN TUBING TO 3060' & SPOTTED 30 SX CMT. PERFORATED 5 1/2" @ 1000'. PUMPED 110 SX CMT DOWN 5 1/2". 0 PRESSURE ON VACUUM. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 1500 PSIG. NO ENTRY. POSSIBLY SQUEEZED. PUMPED ANOTHER 365 SX CMT DOWN 5 1/2". MAXIMUM PRESSURE 250 PSIG. SHUT IN PRESSURE 75 PSIG. 12/15/03: TOC @ 400'. WILL FILL 5 1/2" TO SURFACE WITH 1 1/2 YARDS OF REDIMIX.

RECEIVED
DEC 19 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 12-22-03

BY. NO. 20040609-74

Form CR-211
[Signature]