

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21019-00-01
Spot: SENW\NW Sec/Twnshp/Rge: 14-7S-19W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: REED OWWO Well Number: 1
County: ROOKS Total Vertical Depth: 3471 feet

Operator License No.: 9957
Op Name: THOMASON PETROLEUM, INC
Address: 301 W 13TH ST PO BOX 875
HAYS, KS 67601

Production Casing Size: 4.5 feet: 3410 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 248 w/175 sxs cmt

112 81

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2003 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: STEVE THOMASON Company: THOMASON PETROLEUM, INC. Phone: (785) 623-1174

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel with 500# hulls.
DV at 1375' w/200 sxs cement. Fluid level 1800'.

Plugging Proposal Received By: ROGER MOSES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/15/2003 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied hooked up to backside - instant pressure 500#.
Tied onto 4 1/2" casing - pumped 250 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 700#. S.I.P. 0#.
Checked cement 20' from surface.

RECEIVED
DEC 19 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12-22-03

INV. NO. 2004060977

Form CP-2/3

DEC 17 2003

T & D OIL COMPANY
 BOX 278
 VICTORIA, KS. 67671
 CONTR BILLS WELL SERVICE CTY ROOKS #1 REED "OWWO" 14-7-19W SE NW NW

GEOL _____ FIELD GROVER EXT (1/4 N; 1/2+ FROM PROD)
 E 1953 KB CM 4/28/80 CARD ISSUED 8/7/80 IP P 10 B0 & 27 BWPD
1948 GL LKC 3308-53
 API 15-163-21,019-A

	+	+
	+	+

LOG	TOPS	DEPTH	DATUM
HEEB		3113	-1160
TOR		3135	-1182
LANS		3153	-1200
B KC		3373	-1420
CONG		3394	-1441
ARB		3424	-1471
RTD		3470	-1517
LTD		3471	-1518

OLD INFO: OPERATOR WAS ABERCROMBIE
 DRLG. INC., #1 REED, SPD 2/12/80, SET
 8-5/8" 248/175SX
 DST (1) 3180-3210/30-45-30-30, REC 20'
 THIN M, SIP 789-491#, FP 45-45/45-
 45#
 DST (2) 3227-3265/30-45-60-45, REC
 130', MDY W W/FEW O SPTS, SIP 980-
 1044#, FP 43-65/76-109#
 DST (3) 3303-3318/30-45-60-45, REC 220'
 GIP, 90' MCO (70% O), SIP 863-831#,
 FP 21-32/43-54#
 DST (4) 3321-3346/30-30-30-30, REC 10'
 M, SIP 32-32#, FP 21-21/21-21#
 DST (5) 3343-3370/30-45-30-30, REC 90'
 (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

T & D OIL COMPANY #1 REED "OWWO" 14-7-19W SE NW NW
 THIN M W/O SPTS, SIP 831-565#, FP 76-76/87-87#

NEW INFO: RE-ENTERED 4/28/80, WSH
 DWN TO OTD, SET 4 1/2" 3410/150SX,
 DV TOOL 1375/200SX, MICT - CO, PB
 3389 TD, PF (LKC) 16/3349-53, TST'D,
 PF (LKC) 3308-53, AC 2500 (15%),
 SWB LD W/SO, POP