

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19061-00-00
Spot: NWNENE Sec/Twnshp/Rge: 3-12S-16W
330 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: DREILING F Well Number: 9
County: ELLIS Total Vertical Depth: 3410 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: PO BOX 550 1008 CODY AVE
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3410 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 975 w/400 sxs cmt

\$110.⁸³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2003 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL, INC. Phone: (785) 735-2289

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
CIBP at 2850'.
Emergency plug with rig over the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/03/2003 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2685' - mixed and spotted 125 sxs cement with 500# hulls.
Pulled up to 1386' - circulated cement up 5 1/2" x 8 5/8" annulus.
POOH. Swaged onto and pumped to pressure with 10 sxs cement.
Max. P.S.I. 1400#. S.I.P. 550#.

RECEIVED
DEC 19 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

102.

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12.22.03

UV. NO. 2004060971

DEC 11 2003

