

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20116-00-00  
Spot: S2NWNE Sec/Twnshp/Rge: 13-20S-23W  
660 feet from N Section Line, 1980 feet from E Section Line  
Lease/Unit Name: BETZ B Well Number: 1  
County: NESS Total Vertical Depth: 4348 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: PO BOX 70 234 W. 11TH, STE A  
HAYS, KS 67601

Production Casing Size: 2.375 feet: 4100 WITH 145 SX CMT  
Production Casing Size: 4.5 feet: 4335 WITH 100 SX CMT +  
Surface Casing Size: 8.625 feet: 268 WITH 225 SX CMT  
#14131

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2003 9:45 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: DEAN IVES Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: 1ST PLUG DOWN TUBING PUMP 200# HULLS & 25 SX CMT. 2ND PLUG PERFORATE AT 720'. CIRCULATE 2 7/8" X 4 1/2" FULL OF CMT. SHUT IN. SQUEEZE 4 1/2' WITH 80 SX CMT PLUS CASING VOLUME.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/16/2003 11:45 AM KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**


PERFS AT 4233-36, 4245-50, 4320-24, 4332-40'. OPEN HOLE 4335-4348'. 2 3/8" TUBING CEMENTED IN HOLE @ 4100' WITH 145 SX CMT. PUMPED 25 SX CMT & 250# HULLS TO BOTTOM. PERFORATE AT 720' & PUMPED 82 SX CMT. CIRCULATED BETWEEN 2 3/8" X 4 1/2". SHUT IN 4 1/2" CASING & PUMPED 3 SX CMT DOWN TUBING. PRESSURED TO 800# & HELD. TIED ONTO BACKSIDE OF 4 1/2" & PUMPED 20 SX CMT. PRESSURED TO 500# AND HELD. TIED ONTO TUBING, STILL HAD 600# PRESSURE ON IT. TIED ONTO 2 3/8" X 4 1/2" AND PRESSURE WAS AT 600#.

RECEIVED  
DEC 19 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 12.22.03  
INV. NO. 2004060970

Form CR-3