

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20913-00-00  
Spot: S2S2SE Sec/Twnshp/Rge: 19-16S-29W  
330 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: STEFFENS Well Number: 4  
County: LANE Total Vertical Depth: 4520 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

Production Casing Size: 4.5 feet: 4519 WITH 1175 SX CMT  
Surface Casing Size: 8.625 feet: 448 WITH 300 SX CMT

# 14690

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2003 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL Phone: (316) 263-3535

Proposed Plugging Method: PUMP 25 SX CMT - 200# HULLS - GEL TO 1900'. PUMP CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/17/2003 9:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PERFS AT 4368.5-71.5'. PORT COLLAR @ 1911' WITH 300 SX CMT. PUMPED DOWN 4 1/2" 25 SX CMT WITH 200# HULLS - 12 SX GEL SPACER TO 1900'. PUMP 100 SX CMT TO SURFACE. MAXIMUM PRESSURE 600#. SHUT IN PRESSURE 200#. FELL 400' & TOPPED OFF WITH 25 SX CMT. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 20 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

RECEIVED  
DEC 29 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Kevin D Strube*

(TECHNICAL)  
INVOICED  
DATE 12.29.03  
INV. NO. 2004060999 Form CP-2/3