

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21737-00-00
Spot: NENESE Sec/Twnshp/Rge: 34-18S-29W
2310 feet from S Section Line, 430 feet from E Section Line
Lease/Unit Name: KEENAN Well Number: 1
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 150 N. MAIN, STE 801
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4413 WITH 135 SX CMT
Surface Casing Size: 8.625 feet: 257 WITH 180 SX CMT

151 4/5

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/19/2003 8:00 AM
Plug Co. License No.: 30684 Plug Co. Name: ABERCROMBIE RTD, INC
Proposal Rcvd. from: GERALD Company: ABERCROMBIE RTD, INC Phone: (316) 262-1841

Proposed Plugging Method: PUMP 200# HULLS WITH 25 SX CMT & 11 SX GEL FOR BOTTOM PLUG. FILL 4 1/2" WITH CMT TO SURFACE. PRESSURE TEST. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/19/2003 10:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 4312'. PERFS AT 4295-4298'. PORT COLLAR @ 1415'. PUMP 200# HULLS WITH 25 SX CMT & 11 SX GEL. FILLED 4 1/2" TO SURFACE FROM 2150' WITH 115 SX CMT. PRESSURE TO 400 PSIG & SHUT IN. PUMP 20 SX CMT ON BACKSIDE. SHUT IN AT 300 PSIG.

RECEIVED
DEC 29 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
DEC 22 2003
KCC Dodge City

Signed

Steve Shumant

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-29-03
INV. NO. 2004010997