

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21163-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 25-31S-19W  
790 feet from S Section Line, 1100 feet from W Section Line  
Lease/Unit Name: PROCTOR Well Number: 1-25  
County: COMANCHE Total Vertical Depth: 6000 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: PO BOX 2758 221 N MAIN STE 300  
WICHITA, KS 67201

Conductor Pipe Size: 13.375 feet: 105 WITH 100 SX CMT  
Production Casing Size: 4.5 feet: 5413 WITH 125 SX CMT  
Surface Casing Size: 8.625 feet: 675 WITH 300 SX CMT <sup>00</sup>  
195

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2003 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TIM HOSS Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: CIBP @ 5100' & 2 SX CMT. PLUG AT 1100' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/05/2003 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PERFS AT 5157-63 & 5183-93'. SET CIBP @ 5100' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. AT 3800' PUMPED 30 SX GEL TO KILL WELL. 1ST PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
DEC 23 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4806' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED

DATE 12.24.03  
INV. NO. 2004060986

Form CP-23