

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20800-00-01
Spot: NWSE Sec/Twnshp/Rge: 15-18S-26W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: WALTER "OWWO" Well Number: 1
County: NESS Total Vertical Depth: 4665 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Production Casing Size: 5.5 feet: 4664 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 330 WITH 250 SX CMT

15161

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2003 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed Plugging Method: LOAD HOLE & ESTIMATE RATE. PUMP 200# HULLS & FILL CASING TO SURFACE WITH CMT. PRESSURE TO 500#. FILL 8 5/8" X 5 1/2" WITH CMT. PRESSURE TO 300#.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/10/2003 1:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 4464'. PERFS AT 4458-4461'. DV TOOL @ 1922' WITH 200 SX CMT. CMT CIRCULATED. PUMPED DOWN 5 1/2" CASING 35 SX CMT WITH 200# HULLS, 18 SX GEL & 155 SX CMT. MAXIMUM PRESSURE 2500#. SHUT IN PRESSURE 1500#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#.

RECEIVED
DEC 29 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D Strube

(TECHNICIAN)

INVOICED

DATE

12-29-03

INV. NO.

2004061000

204061000

Form 12/2/03