

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20796-00-00  
Spot: NESESE Sec/Twnshp/Rge: 19-16S-29W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: STEFFENS Well Number: 2  
County: LANE Total Vertical Depth: 4545 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 4544 WITH 175 SX CMT  
Surface Casing Size: 8.625 feet: 328 WITH 250 SX CMT

*8147.71*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2003 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL CO. Phone: (316) 263-3535

Proposed Plugging Method: PUMP 35 SX CMT- 300# HULLS & GEL TO 2150'. PUMP CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/17/2003 12:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 4544'. PERFS AT 4376-4473'. PORT COLLAR @ 2163' WITH 600 SX CMT. TOC @ 750'. PUMPED DOWN 5 1/2" CASING 35 SX CMT & 300# HULLS. DISPLACED WITH 17 SX GEL & 150 BBL WATER. PRESSURED UP TO 500#. PERFORATED 5 1/2" @ 700'. PUMPED 136 SX CMT. SHUT IN @ 0#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 120 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE @ 300#. TOPPED OFF 5 1/2" CMT. CMT 50' DOWN.

RECEIVED  
DEC 29 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED

Plugged through: CSG

District: 01



Signed

*Kevin D Strube*

INVOICED  
DATE 12.29.03  
INV. NO. 2004060999

Form CR 273