

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20751-00-00  
Spot: SESESE Sec/Twnshp/Rge: 19-16S-29W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: STEFFENS Well Number: 1  
County: LANE Total Vertical Depth: 4538 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 4538 WITH 175 SX CMT  
Surface Casing Size: 8.625 feet: 323 WITH 250 SX CMT

*4147 49*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2003 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL Phone: (316) 263-3535

Proposed Plugging Method: PUMP 35 SX CMT & 300# HULLS ON BOTTOM, THEN GEL TO 2150' & CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/17/2003 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 4538'. PERFS AT 4242-4471'. PORT COLLAR @ 2175' WITH 400 SX CMT CIRCULATED. PUMPED DOWN 5 1/2" 35 SX CMT - 300# HULLS - 17 SX GEL & 180 SX CMT. WELL ON VACUUM. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 20 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 500#. CHECK FLUID LEVEL @ 2900'. SET CIBP @ 2150'. PUMPED DOWN 5 1/2" 180 SX CMT. SHUT IN AT 300#.

RECEIVED  
DEC 29 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

*Kevin D Strube*

(TECHNICIAN)

INVOICED

DATE 12-29-03  
# 2004060999

*[Signature]*