

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24963-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 21-14S-19W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: DONALD KRAUS Well Number: 7  
County: ELLIS Total Vertical Depth: 3855 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: PO BOX 2757 202 SOUTH ST. FRANCIS  
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 3846 100 SX CMT  
Surface Casing Size: 8.625 feet: 214 150 SX CMT

# 125 29

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2003 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 250 sxs Swift Multi-Density cement with 500# hulls.  
Fluid level 1600'. PBTB 3855'. O.H. 3846' - 3855'.  
D.V. Tool 1504' cwc.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/22/2003 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services pumped 205 sxs Swift Multi-Density cement with 500# hulls.  
Max. P.S.I. 1600#. S.I.P. 100#.  
Hooked up to backside - instant 500#.

RECEIVED  
DEC 24 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICE  
DATE 12-24-03  
INV. NO. 2004060984

DEC 23 2003

1  
 2  
 3  
 4  
 5  
 6  
 7  
 8  
 9  
 10  
 11  
 12  
 13  
 14  
 15  
 16  
 17  
 18  
 19  
 20  
 21  
 22  
 23  
 24  
 25  
 26  
 27  
 28  
 29  
 30  
 31  
 32  
 33  
 34  
 35  
 36  
 37  
 38  
 39  
 40  
 41  
 42  
 43  
 44  
 45  
 46  
 47  
 48  
 49  
 50  
 51  
 52  
 53  
 54  
 55  
 56  
 57  
 58  
 59  
 60  
 61  
 62  
 63  
 64  
 65  
 66  
 67  
 68  
 69  
 70  
 71  
 72  
 73  
 74  
 75  
 76  
 77  
 78  
 79  
 80  
 81  
 82  
 83  
 84  
 85  
 86  
 87  
 88  
 89  
 90  
 91  
 92  
 93  
 94  
 95  
 96  
 97  
 98  
 99  
 100

replacement card

MICHAEL D WEILERT OIL CO  
HAYS KS 67601

21-14S-19W  
NW SW SW

#7 WITCRAFT-KRAUS

site: 2-3/4 S & 5-1/2 W OF HAYS KS      city: ELLIS      API 15-051-24963  
 contr: DUKE DRILLING #4      field: KRAUS  
 geol: RON NELSON  
 dr date 04/16/97      opd date 05/08/97      drlg comp 05/13/97      card issued 08/04/97      last revised 10/13/97


ELV: 2217 KB, 2208 GL LOG

tops.....	depth/datum
ANH.....	1494 + 723
B/ANH.....	1539 + 678
TOP.....	3225 -1008
HEEB.....	3458 -1241
TOR.....	3499 -1282
LANS.....	3525 -1308
BKC.....	3770 -1553
PBTD.....	3800 -1583
MARM.....	3810 -1593
GORHAM SD.....	3840 -1623
ARB.....	3846 -1629
LTD.....	3852 -1635
RTD.....	3855 -1638

**IP status**  
 OIL, ARB 3846-3855, 07/18/97  
 CORR & INFO REL: 10/13/97 - CORR ELEV PER LOGS  
 (WAS 2189 KB, 2180 GL); WAS OIL WELL - TIGHT  
 HOLE  
 CSG: 8-5/8" 214 (ALT 2), 5-1/2" 3846, MULTI STAGE  
 COLLAR AT 1504  
 NO CORES  
 DST (1) 3829-3845 (GORHAM SD), / 30-30-0-0, REC 1' M  
 ISIP 55# IFP 44# -44# IHP 1995# FHP 1940# BHT 108'  
 DST (2) 3829-3855 (ARB), / 45-45-45-45, 30' GIP, REC 70'  
 CLEAN GSY OIL (90% OIL, 10% G, GR 32), 20' MDY OIL  
 (80% OIL, 20% M), 60' HOCM (30% OIL, 70% M) ISIP  
 1239# FSIP 1228# IFP 66# -88# FFP 99# -110# IHP 2037#  
 FHP 1907# BHT 112'

COPYRIGHT 1997  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

(over)