

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22973-00-00
Spot: NESENW Sec/Twnshp/Rge: 21-14S-19W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: KRAUS DON Well Number: 3
County: ELLIS Total Vertical Depth: 3781 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

Production Casing Size: 5.5 feet: 3375 w/200 sxs cmt
Surface Casing Size: 8.625 feet: 223 w/125 sxs cmt

A 122 88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2003 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 250 sxs Swift Multi-Density cement with 500# hulls.
Fluid level 300'. Perfs 3745'-3753'. O.H. 3778'-3781'.
August 6, 1982 - Alt.II 300 sxs - 1450' to surface.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/22/2003 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Express Well Service ran tubing to 2150'.
Swift Services pumped 170 sxs Swift Multi-Density cement with 500# hulls - cement circulated.
PTOH. Swift squeezed with 45 sxs Swift Multi-Density cement.
Max. P.S.I. 500#. S.I.P. 150#.
Hooked up to backside - instant 800#.

RECEIVED
DEC 24 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

100

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 12-24-03

INV. NO. 2004060984

Form CP-2/3

DEC 22 2003

MICHAEL D. WEILERT
OIL COMPANY
BOX 988

REPLACEMENT CARD

HAYS, KS. 67601

#3 DON KRAUS


21-14-19W
NE SE NW

CONTR HELBERG OIL COMPANY

CTY ELLIS

GEOLOGICAL

FIELD KRAUS



ELV 2148 KB SPD 4/12/82 CARD ISSUED 11/24/82 IP P 50 BQ & 5.6 BWPD
2143 GL
API 15-051-22,973 GORHAM 3745-3753

	Tops	Depth/Datum
SMP		
ANH		1418+ 730
TOP		3124- 976
HEEB		3390-1242
TOR		3409-1261
LANS		3435-1287
MARM		3722-1574
GORHAM		3743-1595
REW ARB		3764-1616
ARB		3773-1625
RTD		3778-1630

8 5/8 " 223 / 125SX, 5 1/2 " 3375 / 200SX
DST (1) 3388-3496 (TOR, LKC) / 60-30-60-30, REC 480' SLI OIL
SPKD MW, SIP 476-453#, FP 125-156 / 164-281#
DST (2) 3581-3653 (LKC) / 60-30-60-30, REC 240' MW, SIP
336-319#, FP 50-84 / 101-126#
DST (3) 3734-69 (MARM, GORHAM) / 60-30-60-30, 180' GIP,
REC 1200' CL GSY OIL, SIP 991-983#, FP 59-286 / 312-413#
DST (4) 3769-74 (ARB) / TOOL PLUGGED, MISRUN
MICT - CO, PF (GORHAM) 3745-53, W / 4 SPF, SWB DWN, SO,
NAT, SET 2 7/8 " TBG AT 3771', POP, P 50 BQ & 5.6 BWPD (GR
34.5°), 5/8/82

INFO RELEASED: 10/17/85 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS