

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20168-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 3-14S-19W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: WIELAND Well Number: 1
County: ELLIS Total Vertical Depth: 3755 feet

Operator License No.: 31240
Op Name: ENTERPRISE INC
Address: 2708 BARCLAY DR.
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3753
Surface Casing Size: 8.625 feet: 150

\$122⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2003 2:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: STEVE WEILERT Company: ENTERPRISE INC. Phone: (785) 625-9699

Proposed
Plugging
Method:

Ordered 300 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/17/2003 5:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 150' w/150 sxs cement. 5 1/2' casing at 3753' with unknown cement.
Tied to 5 1/2" casing - squeezed 260 sxs cement and 500# hulls.
Max. P.S.I. 150#
Tied to 8 5/8" S.P. - squeezed 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 150#.
Total of 275 sxs 60/40 pozmix and 500# hulls.
Dakota 435' to 735'. Anhydrite 1487' - 1527'. Salt 1899' - 2114'.

RECEIVED
DEC 24 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

HD

Signed

Roger Moses

(TECHNICIAN)

INVOICED

DATE 12-24-03

INV. NO. 2004060983

Form CP-2/3

DEC 22 2003

STAD
 UNOICED

C. W. SMITH #1 WIELAND 3-14-19W
 NW NW SE
 Contr. LEBEN DRLG. Cty. ELLIS
 Geol. Pool STADELMAN REVIVAL

E. 2190 KB Cm. 11/21/67 Cp. 12/28/67 IP P 95 BOPD, NW
 LANS 3625-29, 129-130
 3648-52, GRAV 40

AP: 15-051-20,168

LOG Tops	Depth	Datum
ANHY	1487	+ 703
TOP	2188	= 998
HE-B	3448	-1258
TOR	3471	-1201
LANS	3495	-1306
LTD. & RID	3755	-1555

Csg. 8" 150 157-156
 DST 3525-34/1', 190' VHO&GCM, 30'-#2
 (TOOL PARTIALLY PLED) BHP
 939-914#/30", FP 75-91#
 DST 3671-84/1', 600' OW, BHP 175'-185
 770-495#/30", FP 158-315#
 DST 3626-39/1', 3/50", TSTM, 950'
 CL OIL, NW, BHP 1261-1210#/
 30", FP 100-293#
 DST 3549-59/1', 3/20", TSTM, 2600'
 CL OIL, NW, BHP 1283-1230#/
 30", FP 450-788#
 DST 3667-79/1', 1080' GIP, 300' O
 210' WTR, BHP 1200-1120#/30",
 FP 85-251#

CO PF 16/3625-29, 16/3648-52, FU
 INDEPENDENT OIL & GAS SERVICE 3100 OTH/12 HRS, S&B 15 BOPD, NW
 WICHITA, KANSAS NATL, NT, A 2000 EA ZN, R&C LD, S 45 BOPD/9'