

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30246-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 17-14S-14W
2310 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: KRUG-TWIN Well Number: A-1
County: RUSSELL Total Vertical Depth: 3329 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 7 feet: 3328 150 SX CMT
Surface Casing Size: 10.75 feet: 600 350 SX CMT ¹⁹
\$108

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2003 12:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BOB GRANT Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/12/2003 4:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3311'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 700# hulls.
Pulled to 2300'.
Pumped 50 sxs cement with 200# hulls.
Pulled to 1990' and circulated with 200 sxs cement and 100# hulls.
POOH. Pumped 15 sxs cement down backside.
Max. P.S.I. 500#. S.I.P. 500#.
Tied onto casing and pumped 30 sxs cement.
Max. P.S.I. 700#. S.I.P. 500#.

RECEIVED
DEC 24 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 12-24-03
WV. NO. 2004060981

DEC 23 2003

4-170 Map No. REPL. COMP. #1

OPER OKMAR OIL CO.

WICHITA, KS.


WELL #A-1 KRUG (TWIN)

CONTR LEBEN DRLG.

FIELD HALL-GURNEY FIELD (MULTI PAY)

I.P. CO P 25 BOPD + WTR

LAN 3075-3208



S-T-R 17-14S-14W

SPOT SW SW NW

CO RUSSELL (KS)

ELEV 1883 KB

(KB SPL)

TOP 2763 - 880

MB 2994 -1111

TOR 3013 -1130

LAN 3052 -1169

REG 3301 -1418

QTZ SD 3310 -1427

QTZ 3316 -1433

RTD 3329 -1446

SPUD 3-20-66 10" 600/350 SX. GEOL. - MAX HOUSTON

NO DST'S, RTD 3329. NO LOG, 7" 3328 W/150 SX.

CO, PF 12/3075-78, 24/3090-96, 16/3135-39, 8/3206-08

(LAN), 3000A, 8 LD, TEST 5 GOPH + 50% WTR/NT, POP

CO P 25 BOPD + WTR, LAN 3075-3208 - COMPLETED (4-25-66)

REPLACEMENT COMPLETION: (9-22-66)

REPLACED TO CORR SPOT WAS-SW SW NE IS- SW.SW NW

MISCEL DATA

GEOL MAX HOUSTON

ELEV 1881 DF

SPUD DATE 3-20-66

FTG

1879 GR

DRLG COMP

SUPPT

FR by DATA 3-22-66

CSG 10" 600 W/350 SX.

7" 3328 W/150 SX.

COMP by " 4-28-66