

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-38093-00-00
Spot: SESW Sec/Twnshp/Rge: 15-14S-14W
660 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: HERB FINK Well Number: 1
County: RUSSELL Total Vertical Depth: 3310 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Production Casing Size: 5.5 feet: 3250 250 SX CMT
Surface Casing Size: 10.75 feet: 109 70 SX CMT

58
H107

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2003 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: BOB GRANT Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/03/2003 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Fluid level at plus 200'.
Ran tubing to 2050' - stacked out.
Pumped 100 sxs 60/40 pozmix - 10% gel cement.
Pulled to 800'.
Circulated with 80 sxs cement and 200# hulls.
POOH.
Tied onto casing and pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.
Tied onto backside and pumped 35 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
DEC 22 2003

Remarks: ALLIED CEMENTING COMPANY.
KCC WICHITA

Plugged through: CSG

District: 04

10

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 12-24-03
INVOICE NO. 2004060980

DEC 05 2003

STAG
 STAG
 1310VMI

COOPERATIVE REFINERY ASSN #1 ^{Head} FINK ^{15-14-14W} G SE SW

Contr. _____ RUSSELL County

E. _____ Comm. _____ Comp. _____ IP 8 BO & 26 BWPD

Tops	Depth	Datum
ANH	865	
LANS	3031	
GRAN WSH	3290	
TD	3310	

Casing
 10" 109
 7" 3250
 0 W P B
 COMP 12-30-42 FOR
 179 BOPD FROM LANS
 NEW INFO: CO 3168; PERF 28/
 3131-38; 32/3054-62; ACID 6000
 PMP 7.98 BO & 26.37 BWPD

HALL GURNEY POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS