

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04909-00-01  
Spot: NENWSW Sec/Twnshp/Rge: 16-20S-12W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: WORKMAN Well Number: 7  
County: BARTON Total Vertical Depth: 3792 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Production Casing Size: 5.5 feet: 3437  
Surface Casing Size: 8.625 feet: 654  
*\$ 123<sup>24</sup>*

Well Type: SWD UIC Docket No: D06158.0 Date/Time to Plug: 12/19/2003 10:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING COMPANY, IN Phone: (620) 234-5191

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Plug with tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 12/22/2003 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Tubing fish at 430' with set down packer at 3340'.  
Fished for tubing with only pieces being recovered.  
Decision to plug and abandon.  
Ran tubing to top of top of tubing at 450' and circulated cement with 8 bbls cement slurry or 60 sxs.  
Tied onto production casing and pressured to 800#. Held solid.  
Tied onto annulus and pumped 31 bbls slurry or 140 sxs cement. On vacuum.  
12-22-2003:  
Tied onto annulus and pumped 100 sxs cement with 150# hulls.  
Max. P.S.I. 500#. S.I.P. 400#.

RECEIVED  
DEC 24 2003  
KCC WICHITA

Remarks: WELL FORMERLY KNOWN AS OPAL LANTERMAN #7. ALLIED CEMENTING COMPANY-TICKET#14335,143

Plugged through: TBG

District: 04

Signed *Pat Staab*  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-29-03

INV. NO. 2004060991

DEC 23 2003

SKELLY OIL CO

#7

OPAL LANTERMAN NE NW SW

16-20-12W 53

Contr. GLAUDE WENTWORTH DRLG

BARTON

County

E. 1840RB Comm. 7-15-57 Comp. 8-30-57 IP 47 BOPD/ARB

PHY POT

Tops	Depth	Datum
HEEB	3050	-1210
TOR	3060	-1220
KC	3185	-1345
ARB	3435	-1595
ID	3472	-1632

Casing

5" 3436

DD 3472: 1 BOPH & 2 BWPB

WORKMAN NW POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

3010V11