

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01620-00-00
Spot: NENENW Sec/Twnshp/Rge: 10-9S-19W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: ROSTOCIL C Well Number: 7
County: ROOKS Total Vertical Depth: 3441 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

Production Casing Size: 7 feet: 3437 w/90 sxs cmt
Surface Casing Size: 10.75 feet: 560 w/300 sxs cmt

83
\$ 111.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2003 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Plugging Method: Ordered out 450 sxs Swift Multi-Density cement with 600# hulls.
Casing leak at 2385' - 2398'.
Tubing and packer fish at 3775' - unable to fish.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/10/2003 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3100'. Swift Services pumped 150 sxs Swift Multi-Density cement with 200# hulls.
Pulled tubing to 1550'. Swift Services pumped 150 sxs Swift Multi-Density cement with 500# hulls - cement circulated.
PTOH. Swift squeezed with 125 sxs.
Max. P.S.I. 200#. S.I.P. 0#. Shut in one hour.
Cement down 250' - topped off with 25 sxs.
Hooked up to backside - instant 500#.

RECEIVED
DEC 24 2003
KCC WICHITA

Remarks: SWIFT SERVICES, INC. EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVER HOLE.

Plugged through: TBG

District: 04

10

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 12-24-03
WY. NO. 2004060984

DEC 22 2003

SOHIO PETROLEUM CO

#7

ROSTOCK, MO

10-9-194

NE NE NW

Contr.

EMPIRE DRUG

ROOKS

County

E 2033 RB Comm: 4-23-62 Comp:

7-5-62

IP 105 BOPD/ARB

43-80, 18 1/2 W, GR

LOG Tops	Depth	Datum
ANH	1431	-602
HEEB	3149	-1116
TOR	3171	-1138
LANS	3189	-1156
ARB	3435	-1402
LTD	3441	-1408

Casing 36/LANS

10" 560/300 SX

7" 3437

NO TESTS

CO 3441 TD: FD 800' FIH: SWB

47 BOPH, NW: PERE 12/3389-3401

12/3389-92: 16/3364-68: 12/

3349-52: SWB 49 BOPH, NW: ACID

PMP 30 BOPD & 5 BW

BARRY POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS