

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

RECEIVED

DEC 17 2003

KCC WICHITA

API NUMBER 15 -053-00873 -00-00

LEASE NAME Buehler Twin

WELL NUMBER 11

4950' S Ft. from Section Line

2340' E 1320 Ft. from Section Line

NOTICE: Fill out completely

and return to Cons. Div.

office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 33 TWP. 17S RGE. 8W (E) or (W)

ADDRESS 250 N. Water, Ste. 300

COUNTY Ellsworth

Wichita, KS 67202

PHONE # 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 7/3/1955

Character of Well Oil (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 12/5/2003

Plugging Completed 12/5/2003

The plugging proposal was approved on 11/6/03
(date) 12/5/2003

By Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? ? If not, is well log attached? No

Producing Formation NA Depth to Top _____ Bottom _____ TD 3205' Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	203'	<u>12.25</u> <u>8 5/8"</u>	203'	0
	Production		3205'	7"	3205'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Spot 40 sx 60/40 4% gel 150# hulls down tbg @ 3130', pulled to 1100' pumped 35 sx 60/40 4% gel 100# hulls, pulled to 800' pumped 35 sx cement 60/40 4% gel 150# hulls pull to 260' pumped 100 sx 60/40 4% gel 300# hulls, circ cmt to surface. TOH w/tbg. Top off 7" casing w/15 sx. Total cmt pumped 230 sx & 700# hulls.

Name of Plugging Contractor Murfin Drilling Co., Inc. License No. 30606

Address 250 N. Water, Ste. 300 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says:
That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 10th day of Dec. 2003

Notary Public - Barbara Dodson
My Commission Expires: 12-10-03 Form CP-4

Revised 05-88



Federal tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Great Bend

DATE <u>12-4-03</u>	SEC. <u>33</u>	TWP. <u>17</u>	RANGE <u>8 W</u>	CALLED OUT <u>7:00 AM</u>	ON LOCATION <u>9:30 AM</u>	JOB START <u>10:15 AM</u>	JOB FINISH <u>12:30 PM</u>
LEASE <u>Buchler - Twin</u>	WELL # <u>#11</u>	LOCATION <u>K-H + B-1d - Hiway jct - 1 1/2</u>		COUNTY <u>Ellsworth</u>	STATE <u>KS</u>		
OLD OR NEW (Circle one)			<u>North - West - South into</u>				

CONTRACTOR Stewart Well Service - OWNER Martin Drlg Co

TYPE OF JOB Old Hole Plug

HOLE SIZE T.D.

CASING SIZE 6 7/8" x 7" DEPTH

TUBING SIZE 2" DEPTH 3150'

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT

CEMENT

AMOUNT ORDERED 200 3x 60/40 1/2 gel
+ 900 lbs of hulls
used 230 3x cement + 700 lbs hulls -

COMMON	<u>138 mt</u>	@	<u>7.15</u>	<u>986.70</u>
POZMIX	<u>98 mt</u>	@	<u>3.80</u>	<u>372.40</u>
GEL	<u>8 mt</u>	@	<u>10.00</u>	<u>80.00</u>
CHLORIDE		@		
<u>HULLS</u>	<u>700 lb</u>	@	<u>18.00</u>	<u>126.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>267 mt</u>	@	<u>1.15</u>	<u>307.05</u>
MILEAGE	<u>267 mt 05 35</u>			<u>467.25</u>

EQUIPMENT

PUMP TRUCK CEMENTER Jack

120 HELPER T.D.

BULK TRUCK

342 DRIVER Steve

BULK TRUCK

DRIVER

DEC 17 2003 TOTAL 2316.60

REMARKS:

KCC WICHITA SERVICE

1st plug @ 3150' with 35 3x cement +
120 lbs of hulls

2nd plug @ 1100' with 35 3x cement + 100 lbs
of hulls

3rd Plug @ 800' with 35 3x cement
+ 150 lbs of hulls

1/4" plug @ 260' with 100 3x cement +
300 lbs of hulls - Top of well with 15 3x cement
1 thanks

DEPTH OF JOB	<u>3150'</u>		
PUMP TRUCK CHARGE			<u>630.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>35</u>	@	<u>3.50</u>
PLUG		@	
		@	
		@	

TOTAL 752.50

CHARGE TO: Martin Drlg. Co.

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Mark Bohlen

PRINTED NAME