

STATE OF KANSAS
CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-21163-00-00

LEASE NAME PROCTOR

WELL NUMBER 1-25

750 Ft. from S Section Line

1100 Ft. from W Section Line

SEC. 25 TWP. 31 RGE. 19W (E) or (W)

COUNTY Comanche

Date Well Completed 1/27/01

Plugging Commenced 12-5-03

Plugging Completed 12-5-03

DEC 18 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

OPERATOR MULL DRILLING COMPANY, INC.

ADDRESS P.O. Box 2758 Wichita, Kansas 67201

PHONE# (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 8/27/03 (date)

Steve Pfeifer (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>				<u>8-5/8"</u>	<u>675'</u>	<u>None</u>
<u>Prod</u>				<u>4-1/2"</u>	<u>5413'</u>	<u>4806'</u>
<u>Cons</u>			<u>105</u>	<u>13.325</u>	<u>105</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Set CTBP @5100' with 2 sacks cement on top. Cut pipe loose @4806', pulled up to 1100', pumped 10 sacks gel with 50 sacks cement, pulled up to 700', pumped 50 sacks cement, pulled up to 300', pumped 30 sacks cement, pulled rest of pipe and circulated cement to surface. Capped off with 1 sack cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mull Drilling Company, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of December, 20 03

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05