

RECEIVED

DEC 24 2003

KCC WICHITA

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Abercrombie Energy, LLC

ADDRESS Rt. #1, Box 56 Great Bend, Ks. 67530

PHONE# (620) 793-8186 OPERATORS LICENSE NO. 32457

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-11-03 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Lans. KC Depth to Top 3974' Bottom 4339' T.O. 4660'

Show depth and thickness of all water, oil and gas formations. DV Tool @ 1415'KB

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lans. KC.	Oil - Water	4295'	98'	8 5/8	<del>258'</del> 257'	None
				4 1/2	4413'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

Pump 25 sacks 60/40 Poz 6% gel with 100# hulls followed (11 sacks) 33 Bbl. gel spacer to base Anhy & capped with (115 sacks) 45 1/2 Bbl. 60/40 Poz 6% gel. Max press 800# standing  
Pump 25 sacks 60/40 Poz down 8 5/8 - 4 1/2 annulus - shut in with 500# standing.

Name of Plugging Contractor Abercrombie RTD License No. 30684

Address Rt. #1 Box 56 Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Energy, LLC

STATE OF Kansas COUNTY OF Barton, ss.


E. L. Abercrombie

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E L Abercrombie

(Address) Rt. #1, Box 56, Great Bend, Ks. 67530



SUBSCRIBED AND SWORN TO before me this 23rd day of December, 192003

Susan M. Urban  
 Notary Public

My Commission Expires: 7-29-2004