

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15-185-13037-00-00

API NUMBER N/A

LEASE NAME Batman

WELL NUMBER 2

990 N Rev CP 2/3
4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 13 TWP. 21 RGE. X ^{13W} (S) or (W)

COUNTY Stafford

Date Well Completed 7/6/1952

Plugging Commenced 11/20/2003

Plugging Completed 11/20/2003

RECEIVED
DEC 17 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SWNWNE

LEASE OPERATOR White Hawk Oil Company

ADDRESS P. O. Box 3363, Tulsa, Ok 74101

PHONE# (918) 582-1022 OPERATORS LICENSE NO. 5163

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 18, 2003 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? attached

Producing Formation LKC Depth to Top 3414 Bottom 3415 T.D. 3315 PBD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	3530	10-3/4	232	None
				7"	3530	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Perf. w/2 shots 720', 721'. 1st Plug- 2-3/8" @ 2876'. Broke Circ. Mixed 70 sx 60/40 poz, 6% gel, 100# hulls Displaced to balance. 2nd Plug, 2-3/8" @ 740'. Mixed 150 sx 60/40 poz, 6% gel. Circ cement up 7'. Packed off. Mixed 11 sx 60/40 poz, 6% gel, did not circulate. Pulled tubing out of hole. Swedged 7". Hooked up to annulus. Mixed 65 sx 60/40 poz, 2% gel. Shut in-200#.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. N/A-999916

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Hawk Oil Company P.O. Box 1150
Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Rebecca A. Dunlap (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Rebecca A. Dunlap

(Address) P.O. Box 1150, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 16th day of December, 192003

M. Lynne Wooster
Notary Public

My Commission Expires: 4-2-07

