

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA STATE OFF. BUILDING  
130 S MARKET ROOM 2078  
WICHITA KS 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 22 2003

CONSERVATION DIVISION  
WICHITA, KS

WELL PLUGGING RECORD  
K.A.R.-82-3-117

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

15.073-19348.000

API NUMBER 2-7-57

LEASE NAME Derbyshire

WELL NUMBER 8

2590 Ft. from S Section Line

610 Ft. from E Section Line

SEC. 13 TWP. 22S RGE. 10 (E) or (W)

COUNTY Greenwood

Date Well Completed 2-7-57

Plugging Commenced 11-17-03

Plugging Completed 11-17-03

LEASE OPERATOR Schankie Well Service, Inc.

ADDRESS 1006 SW Blvd, PO Box 397 Madison, KS 66860

PHONE (620) 437-2595 OPERATORS LICENSE NO. 6470

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-17-03 (date)

by Mike Heffern, District #3 (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Bartlesville Depth to Top 2094' Bottom 2124' T.D. 2124'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation   | Content | From | To | Size           | Put in       | Pulled out  |
|-------------|---------|------|----|----------------|--------------|-------------|
| <u>Surf</u> |         |      |    | <u>12 1/2"</u> | <u>103'</u>  | <u>None</u> |
| <u>Prod</u> |         |      |    | <u>4 1/2"</u>  | <u>2094'</u> | <u>None</u> |
|             |         |      |    |                |              |             |
|             |         |      |    |                |              |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Plug back bottom to 2040' w/sand, Cap w/5sx cement, shot pipe @ 850' and pump 25sx cement plug, pump gel spacer to 150', shot pipe @ 150', pump 100sx plug to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Schankie Well Service, Inc. License No. 6470

Address 1006 SW Blvd, PO Box 397 Madison, Kansas 66860

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Schankie Well Service, Inc.

STATE OF Kansas COUNTY OF Greenwood, ss.

Randall Schankie, Secretary (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Randall Schankie

(Address) PO Box 397 Madison, KS 66860



SUBSCRIBED AND SWORN TO before me this 28th day of November 2003

Carol R. Bolen  
Notary Public

My Commission Expires: 1-9-2005

DRILLED FOR: L. B. Campbell et al,  
ADDRESS: MADISON, KANSAS

LOCATION: NE NE SE (610' W of E L & 2590' N  
of S L) Section 13-22-10e; Green-  
wood County, Kansas.

CONTRACTOR: Sauder Drilling Co.  
ADDRESS: Gridley, Kansas.

| CASING RECORD: | run   | pulled            | size    |
|----------------|-------|-------------------|---------|
|                | 103'  | left in           | 12 1/2" |
|                | 644'  | 644'              | 10      |
|                | 1277' | 1277'             | 8       |
|                | 2094' | Cemented W/75 Sx. | 4 1/2   |

LEASE NAME: Derbyshire WELL #8

COMMENCED: January 25, 1957  
COMPLETED: February 7, 1957

PRODUCTION: Est. 25 Bbls.

ELEVATION:

TOTAL DEPTH: 2124'

TREATMENT: Sand Frac'd W/25,000# sand

0 to 5' Soil  
45 Shale  
95 Sand (7-BW)  
103 Shale  
108 Lime  
125 Shale  
140 Lime  
195 Shale  
210 Lime  
255 Shale  
260 Lime  
370 Shale  
375 Lime  
405 Shale  
410 Lime  
415 Shale  
430 Lime  
500 Shale  
540 Lime  
595 Shale  
605 Lime  
610 Shale  
618 Lime  
625 Sand  
630 Shale  
640 Lime  
660 Shale  
680 Lime  
710 Shale  
720 Lime  
770 Shale  
780 Lime  
800 Shale  
825 Lime  
840 Shale  
860 Lime  
910 Shale  
915 Sand  
1070 Shale  
1075 Lime  
1105 Shale  
1115 Sand (2-BW)  
1155 Shale  
1270 Lime  
1385 Shale  
1565 Lime (1-BW @1430)  
1680 Shale  
1690 Lime  
1705 Shale

1725 Lime  
1790 Shale  
1800 Lime  
1822 Shale  
1830 Lime  
1840 Shale  
1845 Lime  
1930 Shale  
1940 Lime  
1950 Shale  
1955 Lime  
2091 Shale  
2123 Sand  
2124 Shale  
2124 Total Depth.

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 22 2003

CONSERVATION DIVISION  
WICHITA, KS

This log issued and filed with  
State Geological Society on  
February 16th, 1957.

№ 5158

**Agent of contractor or operator**

THANK YOU

| Sales Ticket for Materials Only |                                   |                      |       |         |  |
|---------------------------------|-----------------------------------|----------------------|-------|---------|--|
| Quantity Sacks                  | BRAND AND TYPE                    |                      | PRICE | TOTAL   |  |
| 125                             | sks                               | 60/40 Pozmix         | 6.50  | 812.50  |  |
| 200                             | lbs                               | Gel (For Gel spacer) | 9.50  | 19.00   |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   |                      |       |         |  |
|                                 |                                   | Handling & Dumping   | .50   | 62.50   |  |
|                                 |                                   | Mileage              | N.C.  |         |  |
| Plugs                           |                                   | Sub Total            |       | 1461.50 |  |
|                                 |                                   | Discount             |       |         |  |
|                                 | Delivered by Truck No. #3         | Sales Tax            | 6.3 % | 92.07   |  |
|                                 | Delivered from EUREKA             | Total                |       | 1553.57 |  |
|                                 | Signature of operator [signature] |                      |       |         |  |