

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-187-20952 0000

LEASE NAME Lucas

WELL NUMBER 1-1211

1320 Ft. from S Section Line

4,620 Ft. from E Section Line

SEC. 11 TWP. 28 RGE. 40 (S or W)

COUNTY Stanton

Date Well Completed 6-22-01

Plugging Commenced 11-14-03

Plugging Completed 11-18-03

DEC 15 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR Te-Ray Energy Inc.

ADDRESS 1105 Sovereign Row Unit C OKC OK 73108

PHONE (405) 232 4121 OPERATORS LICENSE NO. 32855

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-14-03 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Morrow Depth to Top 5318' Bottom 5344' T.D. 5650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Cond</u>				<u>13 3/8</u>	<u>527</u>	<u>-</u>
<u>Subs</u>				<u>8 5/8</u>	<u>1685</u>	<u>-</u>
<u>Prod</u>				<u>4 1/2</u>	<u>5654</u>	<u>2824</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so Mixed 300 lb hulls & 20 sx cmt to plug perfs from 5318 to 5118 Shot & pull 4 1/2 to 1700 Circ. hole w/mud & mixed 50 sx 1700 to 1550 30 sx 600 to 500 10 sx 40 to 0 Cut off & capped 8 3/4 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Ray Energy, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Terry L. Eischen (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Terry L. Eischen

(Address) 1105 Sovereign Row Unit C OKC OK 73108

SUBSCRIBED AND SWORN TO before me this 10th day of December, 2003

Rose M. Newcom  
Notary Public

My Commission Expires

