

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20537-00-00
Spot: NENWSEW Sec/Twnshp/Rge: 10-2S-42W
3945 feet from S Section Line, 3523 feet from E Section Line
Lease/Unit Name: MAUPIN Well Number: 1-10
County: CHEYENNE Total Vertical Depth: 1721 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2711 N. HASKELL - SUITE 2800, IB #22
DALLAS, TX 75204

Surface Casing Size: 7 feet: 350

#5593

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/30/2001 12:00 PM

Plug Co. License No.: 8273 Plug Co. Name: EXCELL DRILLING COMPANY

Proposal Rcvd. from: TOM ROELFA Company: ROSEWOOD RESOURCES, INC. Phone: (214) 756-6600

Proposed Plugging Method: Order 100 sxs 50/50 pozmix - 6% gel.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/30/2003 3:30 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1721' w/50 sxs. Top of plug calculated at 1355'.
2nd. Plug at 400' w/40 sxs. Top of plug calculated at 138'.
3rd. Plug at 60' w/10 sxs.

RECEIVED
JAN 02 2004
KCC WICHITA

Remarks:

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED
DATE 1-2-04
SERIAL 2004061016

DEC 31 2003