

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20101-00-00  
Spot: SENE Sec/Twnshp/Rge: 22-32S-33W  
3400 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: LEMERT Well Number: 1  
County: SEWARD Total Vertical Depth: 5660 feet

Operator License No.: 3062  
Op Name: QUESTA ENERGY CORPORATION  
Address: PO BOX 19297 3601 S. GEORGIA  
AMARILLO, TX 79114

Production Casing Size: 4.5 feet: 5660 WITH 375 SX CMT  
Surface Casing Size: 8.625 feet: 1576 WITH 750 SX CMT

#183<sup>95</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2003 11:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PLUG AT 1600' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/02/2003 11:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 5582'. PERFS AT 5442-5452'. 12/01/03: PUMP 20 SX CMT & 200# HULLS OVER PERFS. 1ST PLUG LOAD HOLE WITH MUD. SPOT 50 SX CMT AT 1600'. GOOD CIRCULATION. 12/02/03: 2ND PLUG PULL TO 500' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED  
JAN 02 2004  
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 2483' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

*Steve Middleton*

INVOICED  
(TECHNICIAN)  
DATE 1-2-04  
REL. NO. 2004061014

Form CP 203  
*[Signature]*