

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20597-00-01
Spot: SWNE Sec/Twnshp/Rge: 5-24S-8W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: CROW Well Number: 1
County: RENO Total Vertical Depth: 4143 feet

Operator License No.: 5585
Op Name: CLINTON PRODUCTION, INC.
Address: 330 NORTH ARMOUR
WICHITA, KS 67206

Production Casing Size: 4.5 feet: 3830
Surface Casing Size: 8.625 feet: 264

\$134⁶⁵

Well Type: EOR UIC Docket No: E25607.1 Date/Time to Plug: 12/22/2003 2:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3400' and 4 sacks; 35 sacks @ 1300'; 35 sacks @ 800'; and 315' to 0'.

RECEIVED
KCC DISTRICT #2
DEC 31 2003

WICHITA, KS

Plugging Proposal Received By: JACK LUTHI

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/22/2003 2:30 PM

KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3400' and 4 sacks of common. Shot 4-1/2" casing off at 2640'. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 800' and pumped 35 sacks of cement. Pulled to 315' and circulated cement to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 05 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET #14332

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE 1-5-04

INV. NO. 2004061020