

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21717-00-00
Spot: W2E2SW Sec/Twnshp/Rge: 8-26S-5E
1290 feet from S Section Line, 1650 feet from W Section Line
Lease/Unit Name: BATMAN A Well Number: 29
County: BUTLER Total Vertical Depth: 2475 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 4.5 feet: 2473 250 SX CMT
Surface Casing Size: 8.625 feet: 255 175 SX CMT

\$ 80⁴⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2003 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2

DEC 23 2003

WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2003 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Spotted 75 sacks at 2437' of common with 3% cc. Pulled tubing to surface and ran tubing with packer to 450'. Test casing to 500 lbs. Pulled tubing and packer to surface. Pumped 323 sacks of 60/40 pos mix with 4% gel down casing. Circulated cement from 580' (hole) to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 05 2004

CONSERVATION DIVISION
WICHITA, KS

Remarks: UNITED TICKET #4914

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE

1-5-04

INV. NO.

2004061027