

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19466-00-00  
Spot: SWNW Sec/Twnshp/Rge: 23-27S-7E  
3300 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: KEIGHLEY Well Number: 27  
County: BUTLER Total Vertical Depth: 3160 feet

Operator License No.: 32081  
Op Name: SMOKEY VALLEY RESOURCES, INC.  
Address: 212 E. SUNDERLAND - PO BOX 199  
CHASE, KS 67521

Conductor Pipe Size: 8.625 feet: 128 60 SX CMT  
Production Casing Size: 4.5 feet: 3118 TO SURFACE 80 SX.  
Surface Casing Size: 5.5 feet: 3150 200 FIBRE 20 IN COR.

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2003 5:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

30 sacks above perms; circulate 250' - 0'; 4-1/2" liner cemented in 5-1/2"; 4-1/2" x 8-5/8" annulus cemented.

RECEIVED  
KCC DISTRICT #:

DEC 30 2003

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER  
Date/Time Plugging Completed: 12/29/2003 5:30 PM

Witness Type: Plugging Operations Were Not Witnessed  
KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

Spotted 30 sacks of cement at 3123' to cover Viola perms. Spotted 30 sacks of cement at 2118' to cover KC perms. Circulated from 250' - 0'.

60/40 poz mix with 4% gel.

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 05 2004


CONSERVATION DIVISION  
WICHITA, KS

Remarks: UNITED CEMENTING

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

INVOICED

DATE 1-5-04

INV. NO. 2004061026