

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-11300-00-0
Spot: ~~NENENW~~ SWSWSE Sec/Twnshp/Rge: 31-25S-13W
4950 feet from N Section Line, 2970 feet from W Section Line
Lease/Unit Name: SHOOP Well Number: 1
County: STAFFORD Total Vertical Depth: 4300 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 5.5 feet: 4200 WITH 125 SX CMT
Surface Casing Size: 8.625 feet: 311 WITH 275 SX CMT

#139⁷⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2003 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRAIN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: 1ST PLUG RUN TUBING TO 4100'. PUMP 200# HULLS & 25 SX CMT, OR SAND CASING TO 4080' & 5 SX CMT OR IF CASING HAS NO HOLES, MIX & PUMP 200# HULLS & 30 SX CMT. DISPLACE TO 4100'. 2ND PLUG TEST CASING TO 300#. PERFORATE @ 1300'. CIRCULATE CMT TO 0' INSIDE & OUT OF 4 1/2".

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/04/2003 10:32 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:
PBTD 4189'. PERFS AT 4138-4144'. CMT BETWEEN 5 1/2" X 4 1/2" AT SURFACE. 12/03/03: SANDED TO 4080' & 5 SX CMT. PRESSURED TESTED 4 1/2" TO 300 PSIG. PERFORATED AT 1300'. PUMPED 110 SX CMT DOWN 4 1/2" HAD SMALL AMOUNT OF CIRCULATION UP 8 5/8" X 5 1/2" ANNULUS. PUMPED 160 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 100 PSI. SHUT IN PRESSURE 100 PSI. ATTEMPTED TO FILL 4 1/2" WITH 130 SX CMT. SHUT DOWN 4 1/2" X 8 5/8" ON VACUUM. 12/04/03: PUMPED 15 SX CMT DOWN 4 1/2". MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG. PUMPED 150 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG.

RECEIVED
DEC 09 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GLE BY COPELAND ACID. NO CASING RECOVERED.
Plugged through: CSG

District: 01
RECEIVED
DEC - 8 2003
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 12.9.03
INV. NO. 2004060878

Form *[Signature]*