

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22981-00-00
Spot: NWN*WNE Sec/Twnshp/Rge: 20-6S-20W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: STATES Well Number: 5
County: ROOKS Total Vertical Depth: 3755 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

Production Casing Size: 4.5 feet: 3751 150 SX CMT
Surface Casing Size: 8.625 feet: 235 165 SX CMT

#122⁰⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2003 9:00 AM
Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC
Proposal Rcvd. from: CHARLEY FARR Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 8% gel - 500# hulls.
Fluid level 1000'. Production perfs 3728' - 3739'. Tubing stuck at 2150'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2003 11:50 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 75 sxs neat cement, followed with 100 sxs with 100# hulls.
Max. P.S.I. 1500#. S.I.P. #200#.
Hooked up to backside.
Allied pumped 10 sxs cement - 500# instant.

RECEIVED
JAN 05 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed

Richard Williams
(TECHNICIAN)

INVOICED

DATE

1-5-04

INV. NO.

2004061024

Form CP-2/3

JAN 02 2004

replacement card

LIBERTY OPERATIONS AND COMPLETIONS, INC
PLAINVILLE, KS 67663

20-06 -20W
NW NW NE

#5 STATES

site: 9 N & 2 E OF NICODEMUS, KS
contr: EMPHASIS OIL OPERATIONS
geol: CHRIS MRAZ

city: ROOKS
field: TODD NE

API-15-163-22981

fr date 01/26/88 spd date 02/24/88 drlg comp 03/01/88 card issued 05/11/88 last revised 05/24/89

ELV: 2242 KB LOG
 tops.....depth/datum
 *DAK SD.....1049 +1193
 *B/DAK SD.....1125 +1117
 *CED HILL.....1375 +867
 *B/CED HILL.....1578 +664
 ANH.....1852 +390
 B/ANH.....1884 +358
 TOP.....3250 -1008
 HEEB.....3450 -1208
 TOR.....3474 -1232
 LANS.....3486 -1244
 BKC.....3679 -1437
 MARM.....3694 -1452

IP status:

OIL, P 10 BOPD, NW, ARB 3728-3739 OA,
ARB.....3715 -1473
RTD.....3755 -1513
*SAMPLE TOP

INFO RELEASED: 5/24/89 - WAS OIL WELL - TIGHT HOLE
CSG: 8-5/8" 235 / 165 SX, 4-1/2' 3751 / 150 SX
NO CORES

DST (1) 3680-3737 (ARB), / 60-60-60-60, REC 105' MDY
OIL (61% OIL, 39% M) ISIP 408# FSIP 397# IFP 58#
70# FFP 70# -81#

MICT - CO, PF (ARB) 3728-3732, 3736-3739, W / 3 SPF,
AC 500 GAL (15% INS) & 750 GAL (15% DS/FE, W 5%
CKRSOL) & 1500 GAL (15% AOG) & 200 GAL (5%
CKRSOL), SO, SET 2-3/8" TBG AT 3733, NO PKR, POP, P
10 BOPD, NW, 3/14/88

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS