

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20589-00-00  
Spot: W2SW Sec/Twnshp/Rge: 7-17S-8W  
1320 feet from S Section Line, 670 feet from W Section Line  
Lease/Unit Name: RATHBUN Well Number: 1  
County: ELLSWORTH Total Vertical Depth: 3294 feet

Operator License No.: 30139  
Op Name: INTERIOR OIL CORPORATION  
Address: 12205 FIRESIDE CT.  
DERBY, KS 67037

Production Casing Size: 5.5 feet: 3293 350 SX CMT  
Surface Casing Size: 8.625 feet: 267 175 SX CMT

# 107<sup>06</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/17/2003 10:00 AM  
Plug Co. License No.: 31073 Plug Co. Name: MAIER WELL SERVICE, INC.  
Proposal Rcvd. from: RON SCHRADER Company: ELLSWORTH SYSTEMS, INC. Phone: (316) 682-1537

Proposed Plugging Method: Sand to 2115' and 5 sacks of cement on top. Perforate at 1150', 775', and 320'. Run tubing to 1150' and pump 35 sacks of cement. Pull tubing to 775' and pump 35 sacks of cement. Pull tubing to 320' and circulate cement to surface.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 12/17/2003 1:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand off perfs to 2115' and put 5 sacks of cement on top. Perforate at 1150', 775', and 320'. Run tubing to 1150' and pump 35 sacks of cement. Pull tubing to 775' and pump 35 sacks of cement. Pull tubing to 320' and circulate cement to surface.

60/40 poz mix with 4% gel.

RECEIVED  
KCC DISTRICT #2

DEC 17 2003

WICHITA, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 05 2004

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENT TICKET #14330

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE: 1-5-04  
INV. NO: 2004061022