

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01844-00-01
Spot: NESENW Sec/Twnshp/Rge: 6-10S-23W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: GANO Well Number: 9
County: GRAHAM Total Vertical Depth: 4025 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

Production Casing Size: 5.5 feet: 4014 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 205 w/150 sxs cmt
130 81

Well Type: EOR UIC Docket No: E13102.3 Date/Time to Plug: 12/18/2003 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RICHARD L. WALLGREN Company: HANSEN, DANE G. TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 400# hulls.
Well squeezd at 1250' and cemented to surface with 250 sxs.
The well had 60 sxs gel in the annulus.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/18/2003 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3100' - mixed and pumped 65 sxs cement with 400# hulls.
Pulled up to 2100' - spotted 40 sxs cement.
Pulled up to 1350' - spotted 25 sxs cement.
Pulled up to 250' - circulated cement with 35 sxs cement.
POOH. Topped off with 20 sxs cement.

RECEIVED
DEC 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 12-30-03

INV. NO 2004061003

Form CP-2/3

DEC 23 2003

D G HANSEN

#9 GANO

6-10-23W
NE SE NW

Contr. C-G DRLG

GRAHAM

County

E 2456 RB Comm. Comp. 3-2-62 IP 132 BOPD, NW, GR

40/LANS 3970-76 &

Tops	Depth	Datum
ANH	2065	+391
TOP	3542	-1086
HEEB	3758	-1302
TOR	3782	-1326
LANS	3795	-1339
B/KC	4020	-1564
TD	4025	-1569

Casing 3951-59
 8" 197
 5" 4012
 DST 3818-44/1 HR, 120' WTRY M, F SPKS O,
 BHP 1310-1260#/20": DST 3858-70/1 HR,
 2030' GIP, 910' GSY O, BHP 1100-1010#/20"
 DST 3881-90/30", 10' M, NO BHP: DST
 3943-58/1 HR, 1860' GIP, 600' GSY O, BHP
 440-430#/20": DST 3955-80/30", 405' G,
 135' OCM, 240' FROGGY O, BHP 540-450#/20"
 DST 3977-96/2 HRS, 30' WTRY M, SG O,
 300' WTRY M, BHP: 950-910#/20":
 CO 3981: PERF 25/3970-76: 10 GOPH: ACID
 2000: 5 BOPH: PLUG 3965: 37/3951-59:
 HOOF NW POOL 5 BOPH, NATL: ACID 2000:
 6 BOPH: CO 3984

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

HANSEN

510