

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20075-00-00
Spot: NW Sec/Twnshp/Rge: 16-4S-40W
1000 feet from N Section Line, 1000 feet from W Section Line
Lease/Unit Name: HARKINS Well Number: 1-16
County: CHEYENNE Total Vertical Depth: 1352 feet

Operator License No.: 31609
Op Name: PRIORITY OIL & GAS LLC
Address: PO BOX 27798
DENVER, CO 80227

Production Casing Size: 4.5 feet: 1318 100 SX CMT
Surface Casing Size: 8.625 feet: 155 140 SX CMT

\$43.94

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/19/2003 3:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ANDY PETERSON Company: PRIORITY OIL & GAS LLC Phone: (785) 332-0101

Proposed
Plugging
Method:

Ordered 120 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/19/2003 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs 1214' - 1236' - one shot - TD 1352'.
8 5/8" surface casing set at 155' w/140 sxs cement.
4 1/2" production casing set at 1318' w/100 sxs cement.
Connected to 4 1/2" production casing - pumped 75 sxs cement with 200# hulls.
Max. P.S.I. 850#. S.I.P. 850#.
Connected to 8 5/8" surface casing - pumped 20 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

RECEIVED
DEC 30 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14304.

Plugged through: CSG

District: 04

10

Signed

Darrel Dipman PART 1
(TECHNICIAN)

INVOICE

DATE 12-30-03

WELL NO. 2004061004

Form CP-2/3

DEC 22 2003

