

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21086-00-00
Spot: NENWNE Sec/Twnshp/Rge: 5-24S-8W
330 feet from N Section Line, 1650 feet from E Section Line
Lease/Unit Name: CROW Well Number: 1-A
County: RENO Total Vertical Depth: 3735 feet

Operator License No.: 5585
Op Name: CLINTON PRODUCTION, INC.
Address: 330 NORTH ARMOUR
WICHITA, KS 67206

Production Casing Size: 5.5 feet: 3730 150 SX COMMON CMT
Surface Casing Size: 8.625 feet: 255 250 SX CMT

\$ 121³⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2003 11:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP 3440' & 4 sacks; 35 sacks @ 1320'; 35 sacks @ 800'; 305' to 0'.

RECEIVED
KCC DISTRICT #2
DEC 31 2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/18/2003 3:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3440' and 4 sacks of cement. Shot 5-1/2" casing off at 2640'. Pulled to 1320' and pumped 35 sacks of cement. Pulled to 800' and pumped 35 sacks cement. Pulled to 305' and pumped cement to surface.

60/40 poz mix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 05 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET #14332

Plugged through: CSG

District: 02

Signed Jack L Luthi
(TECHNICIAN)

INVOICED
DATE 1-5-04
INV. NO. 2004061020