

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

DEC 15 2003

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior

Address: P.O. Box 399, Garden City, Ks 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: December 1, 2003 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Depth to Top: 4138' Bottom: 4189' T.D. 4300'

API Number: 15 - 185-11 300 - 00-00

Lease Name: Shoop

Well Number: #1

Spot Location (QQQQ): SW SW SE NE - NE - NW

4950 Feet from North / South Section Line

2970 Feet from East / West Section Line

Sec. 31 Twp. 25 S. R. 13 East West

County: Stafford

Date Well Completed: 6/15/1944

Plugging Commenced: December 3, 2003

Plugging Completed: December 3, 2003

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Surface and Production formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

M.I.R.U. Run bailer to bottom (4189'). Fluid 1100' from surface. Sand well back to 4080'. Use 60 bbl. total to chase sand down. Spot in tubing. Run in 3 times with bailer to spot 5 sx cement on bottom. Loaded hole - pressured up to 300# - bled off to 100#. Run wireline gun 3 times before it went off to perforate @1300'. Tie on with pump truck and pumped 110 sx cement down casing. Tie on backside - pump 160 sx down surface - another 130 sx down casing to top well off. (60/40 pos. w/6% gel. ) Rigged down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901

Address: P.O. Box 231, Claflin, Ks 67525

Name of Party Responsible for Plugging Fees: American Warrior

State of Kansas County, Barton, ss.

Edward S. Nernich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL Notary Public - State of Kansas My Appt Expires 4/13/06

Edward S. Nernich (Signature)

(Address) P.O. Box 231, Claflin, Ks 67525

SUBSCRIBED and SWORN TO before me this 12th day of December, 2003

Signature of Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202