

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
130 S. MARKET, - ROOM 2078
WICHITA, KANSAS 67202-3802

RECEIVED
DEC 19 2003
KCC WICHITA

API NUMBER 15-093-21731-00-00
LEASE NAME CRC Wood
WELL NUMBER CRC Wood 1
330
320 feet from N/S Section Line
1065 feet from E/W Section Line
SEC 4 TWP 21S RGE 38 E/W
COUNTY KEARNY
Date Well Completed 11-30-2003
Plugging Commenced 12-01-2003
Plugging Completed 12-01-2003
Producing Formation _____
Depth to Top _____
Depth to Bottom _____
T.D. 4950'
If not is well log attached ? _____

WELL PLUGGING RECORD K.A.R.-82-3-117

Type or Print Notice: Fill out completely and return to Cons Div office within 30 days

Lease Operator PETROSANTANDER (USA) INC
Address 6363 Woodway #350,
Address Houston, Texas 77057
Phone 713-784-8700
Operators License 32198
Character of Well D/A (Oil, Gas, D&A, SWD, Water Supply)
The plugging proposal was approved on 12-01-2003 (date)
by Kevin Strubbe (KCC District Agent's Name)
Is ACO-1 filed? Enclosed

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	451'	8-5/8"	10 jts 23#	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Filled with heavy mud, 1st Plug @ 3000' w/100 sks,
2nd Plug @ 2300' w/50 sks
3rd Plug @ 1200' w/80 sks 4th Plug @ 450' w/50 sks
5th Plug @ 40' w/10 sks Total 290 sks 60-40 Poz 6% gel, 1/4# floseal

Name of Plugging Contractor Allied Cementing Co Inc Cheyenne License No. 5382 N/A 97776
Address 24 Sth Lincoln, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PETROSANTANDER
STATE OF TEXAS COUNTY OF HARRIS, ss.

JASON SIZEMORE (Employee of Operator) or (Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature [Signature] Address 6363 Woodway #350, Houston, Texas 77057

SUBSCRIBED AND SWORN TO before me this 15th day of December, 20 003

Notary Public Alan Edwards

My Commission Expires Sept 19th / 2007

