

STATE OF KANSAS  
CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R. - 82-3-117

API NUMBER 15-007-22660-00-00

LEASE NAME Lee Ranch

WELL NUMBER 1-5 TWIN

400 Ft. from S Section Line

360 Ft. from E Section Line

SEC. 5 TWP. 30 RGE. 15W (E) or (W)

COUNTY Barber

Date Well Completed 7-31-01

Plugging Commenced 12-8-03

Plugging Completed 12-15-03

RECEIVED  
DEC 29 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

OPERATOR ABERCROMBIE ENERGY, LLC.

ADDRESS Rt. 1 Box 56 Great Bend, Kansas 67530

PHONE (620) 793-8186 OPERATORS LICENSE NO. 32457

Character of Well Gas

(i.e., Gas, D&A, SWD, Input, Water Supply Well)

This plugging proposal was approved on \_\_\_\_\_ (date)

Scott Alberg (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.O. 4750'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>346</u>	<u>8-5/8"</u>	<u>346'</u>	<u>None</u>
<u>Prod</u>			<u>4746</u>	<u>4-1/2"</u>	<u>4746'</u>	<u>3410'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4500' and 4 sacks cement. Cut pipe loose @ 3410', pulled up to 1278', pumped 10 sacks gel and 50 sacks cement, pulled up to 728', pumped 50 sacks cement. Ran in 350' of 2" tubing and pumped 50 sacks cement, pulled tubing to 40' and circulated 25 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Abercrombie Energy LLC.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 2003

[Signature]  
Notary Public

My Commission Expires:

