

RECEIVED
NOV 10 2003
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-185-22-464-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-21-87

Well Operator: L.D. Drilling, Inc. KCC License #: 6039
(Owner / Company Name) (Operator's)

Address: 7 SW 26 Ave City: Great Bend

State: Kansas Zip Code: 67530 Contact Phone: (620) 793 - 3051

Lease: IVY Well #: 1 Sec. 18 Twp. 22 S. R. 11 East West

NE - SW - NW Spot Location / QQQQ County: Stafford

3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4290 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 344' Cemented with: 250 Sacks

Production Casing Size: 5 1/2" Set at: 3636' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: CIBP 3620'; 3540 - 3550

Elevation: 1831 (G.L. / K.B.) T.D.: 3645' PBTD: _____ Anhydrite Depth: 580 (+1257), 600 (+1237)
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pull 5 1/2" pipe and plug as directed by KCC

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Mike Kasselmann

Phone: (620) 793 - 3051

Address: 7 SW 26 Ave City / State: Great Bend, KS

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____
(Company Name) (Contractor's)

Address: 24 S Lincoln St, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11-07-03 Authorized Operator / Agent: L.D. Davis
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

NOV 10 2003

KCC WICHITA

DRILLERS WELL LOG 15-185-22464-00-00

DATE COMMENCED: September 21, 1987
DATE COMPLETED: September 27, 1987

L. D. Drilling, Inc.
Ivy #1
NE SW NW Sec. 18-22-11
Stafford County, Ks.

Elevation: 1837 K.B.

0 - 493 Sand & Red Bed
493 - 1750 Shale-Lime streaks & rock
1750 - 2616 Lime & shale
2616 - 2794 Shale & lime
2794 - 3365 Lime & Shale
3365 - 3457 Lime
3457 - 3636 Lime & Shale
3636 - 3645 Arb.

FORMATION DATA

Anhy. (Top)	580	(+1257)
Anhy. (Base)	600	(+1237)
Heebner	3110	(-1274)
Toronto	3130	(-1294)
Douglas	3146	(-1310)
B. Lime	3243	(-1407)
Lans. K/C	3267	(-1431)
Base K/C	3496	(-1660)
Cong.	3516	(-1680)
Viola	3540	(-1704)
Simp.	3584	(-1748)
Arb.	3636	(-1800)

Surface Pipe: 8 5/8" new 20# @ 344'
with 250 sx. 50/50 posmix, 2% gel,
3% CC.

Production Csg. 5 1/2" set @ 3636 with
125 sx. 50/50 1/2 pzmix, 18% salt .75 CFR2
20 bbl salt flush.

A F F I D A V I T


STATE OF KANSAS ss
COUNTY OF BARTON

Greg Davidson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 22nd day of October, 1987

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

L.D. Drilling, Inc.
RR 1 Box 183B
7 SW 26th Avenue
Great Bend, KS 67530-9801

November 12, 2003

Re: IVY #1
API 15-185-22464-00-00
NESWNW 18-22S-11W, 3630 FSL 4290 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor