

RECEIVED

NOV 04 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-173-20,733-DD-DD (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *6/04*

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Fenster WELL# 2 SEC. 12 T. 29 R. 1 (East/West)

SE. NW. NE SPOT LOCATION/0000 COUNTY Sedgwick

4290 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

4290¹⁶⁵⁰ FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 217 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3614 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3274-81' Mississippi

ELEVATION 1291 T.D. 3614 PBD 3583 ANHYDRITE DEPTH ?
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Dump sand to 3334', dump bail 4 sax cement, shoot and pull pipe, run in hole tubing to 267', and circulate cement to surface. 60/40 poz 6% gel.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Dick Schremmer PHONE# (316) 524-1225

ADDRESS P.O. Box 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Braden Petroleum & Well Plugging KCC LICENSE # 6957
(company name) (contractor's)

ADDRESS P.O. Box 282, Burden, KS 67019 PHONE # (620) 438-2856

PROPOSED DATE AND HOUR OF PLUGGING (if known?) unknown 10-20-03 plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-1-03 AUTHORIZED OPERATOR/AGENT: [Signature] (signature)