

NOV 04 2003  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-173-20287-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/04

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419  
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE Farber WELL# 3 SEC. 17 T. 29 R. 2 (East/West)

SE NE SW SPOT LOCATION/0000 COUNTY Sedgwick

1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 139 CEMENTED WITH 100 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3501 CEMENTED WITH 75 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3501-12' Simpson

ELEVATION 1325 T.D. 3512 PBD 3512 ANHYDRITE DEPTH ?  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Dump sand to 3461', dump bail 5 sax cement, pull pipe, run tubing to 189', circulate cement to surface. 60/40 poz 6% gel.

(If additional space is needed attach separate page)

Title

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schremmer PHONE# (316) 524-1225  
ADDRESS P.O. Box 438 City/State Haysville, KS 67060

PLUGGING CONTRACTOR Braden Petroleum & Well Plugging KCC LICENSE # 6957  
(company name) (contractor's)  
ADDRESS P.O. Box 282, Burden, KS 67019 PHONE # (620) 438-2856

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown 10-20-03 Plugged

PAYMENT OF THE PLUGGING FEE (K.S.A. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8-1-03 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)