

RECEIVED

NOV 04 2003

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-21449-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/04

WELL OPERATOR Bear Petroleum, Inc. KCC LICENSE # 4419
(owner/company name) (operator's)

ADDRESS P.O. Box 438 CITY Haysville

STATE KS ZIP CODE 67060 CONTACT PHONE # (316) 524-1225

LEASE G. Britton WELL# 1 SEC. 8 T. 26 R. 18 (East/West) (West)

200'-N of - NE - SE SPOT LOCATION/QQQQ COUNTY Edwards

2180 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 338 CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 4800 CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Kinderhook 4672-82', Miss 4620-30', Cottonwood 2972-7
Wreford 2746-52', Winfield 2496-2506', Krieder 2428-38', CIBP 2650'
ELEVATION 2179 T.D. 4800 PBT 2650 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING POH rods and tubing, sand back to 2378', dump bail 4 sax cement, shoot and pull pipe, spot 50 sax at 1200', 50 sax at 340', and 10 sax at 40', all 60/40 6% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dick Schremmer PHONE# (316) 524-1225

ADDRESS P.O. Box 438 City/State Haysville, KS

PLUGGING CONTRACTOR D S & W Well Service KCC LICENSE # 6901
(company name) (contractor's)

ADDRESS P.O. Box 231, Claflin, KS 67525 PHONE # (620) 463-5116

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) unknown 10-6-03 10:00 am plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-30-03 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)